

STUDY OF NONTHERMAL EMISSION FROM SNR RX J1713.7–3946 WITH SUZAKU

TAKAAKI TANAKA^{1,2}, YASUNOBU UCHIYAMA¹, FELIX A. AHARONIAN^{3,4}, TADAYUKI TAKAHASHI^{1,5}, AYA BAMBA¹, JUNKO S. HIRAGA⁶, JUN KATAOKA⁷, TETSUICHI KISHISHITA^{1,5}, MOTOHIDE KOKUBUN¹, KOJI MORI⁸, KAZUHIRO NAKAZAWA⁵, ROBERT PETRE⁹, HIROYASU TAJIMA², AND SHIN WATANABE¹

Draft version June 9, 2008

ABSTRACT

We present results obtained from a series of observations of the supernova remnant RX J1713.7–3946 by the *Suzaku* satellite which cover about two-thirds of the remnant surface. Hard X-rays have been detected from each pointing up to ~ 40 keV. The hard X-ray spectra are described by power-law functions with photon indices of ~ 3.0 , which are larger than those in the energy region below 10 keV. The combination of the spatially-integrated XIS and HXD spectra clearly reveals a spectral cutoff in the X-ray spectrum which is linked to the maximum energy of accelerated electrons emitting synchrotron radiation. The broad-band coverage of *Suzaku* observations from 0.4 keV to 40 keV allows us to derive, for the first time, the energy spectrum of parent electrons in the cutoff region. The inferred cutoff energy in the spatially-integrated X-ray spectrum indicates that the electron acceleration in the remnant proceeds close to the Bohm-diffusion limit. We discuss implications of the spectral and morphological properties of *Suzaku* data in the context of the origin of nonthermal emission. The *Suzaku* X-ray and the H.E.S.S. TeV gamma-ray data together hardly can be explained within a pure leptonic scenario, unless we introduce an additional component of relativistic electrons with softer energy spectrum. Moreover, the leptonic models require very weak magnetic field which does not agree with the recently discovered filamentary structure and short-term variability features of the X-ray emitting region. The hadronic models with strong magnetic field provide perfect fits to the observed X-ray and TeV gamma-ray spectra through the synchrotron radiation of electrons and p - p interactions of protons, but require special arrangements of model parameters to explain the lack of thermal component of X-ray emission. For the morphology studies, we compare the X-ray and TeV gamma-ray surface brightness maps using the *Suzaku* XIS and the H.E.S.S. data. We confirm the previously reported strong correlation between X-ray and TeV gamma-ray emission components. At the same time the *Suzaku* data reveal a deviation from the general tendency, namely, the X-ray emission in the western rim regions appears brighter than expected from the average X-ray to gamma-ray ratio.

Subject headings: acceleration of particles — ISM: individual(RX J1713.7–3946) — ISM: supernova remnants — X-rays: ISM

1. INTRODUCTION

Supernova remnants (SNRs) have long been considered to be likely acceleration sites of cosmic-ray particles below the energy of the *knee*, $\sim 10^{15}$ eV. The energy supply to explain the energy density of cosmic rays is satisfied if ~ 1 –10% of the energy of each supernova is transferred to accelerated particles. Also, the well developed theory of diffusive shock acceleration nicely explains the universal power-law spectrum of cosmic rays (e.g. Blandford & Eichler 1987; Malkov & Drury 2001). Although synchrotron emission detected in the radio band supports this idea observationally, no

evidence of acceleration to TeV energy had been observed until recently. During the last decade, such evidence was revealed through observations of X-rays and TeV gamma rays from several shell-type SNRs. Koyama et al. (1995) discovered synchrotron X-rays from the shell of SN 1006, which indicates electrons are accelerated up to multi-TeV energies. This finding was followed by detections of synchrotron X-rays from other SNRs, including RX J1713.7–3946 (e.g. Koyama et al. 1997; Slane et al. 2001). Further evidence for multi-TeV particles (electrons and/or protons) has been provided by discovery of TeV gamma rays from some SNRs, such as Cassiopeia A (Aharonian et al. 2001) or RX J1713.7–3946 (Muraishi et al. 2000), although their spectral parameters and morphologies were not well determined due to the limited sensitivity of TeV observatories. Subsequently, high quality morphological and spectral studies have been performed by H.E.S.S. (e.g. Aharonian et al. 2004, 2006, 2007). These pioneering measurements by the H.E.S.S. telescope, together with the high resolution X-ray data, have enabled direct comparison of X-ray and TeV gamma-ray data.

The shell-type SNR RX J1713.7–3946 (also known as G347.3–0.5), is one of the best-studied SNRs from which both non-thermal X-rays and TeV gamma rays are detected. This SNR was discovered in soft X-rays during the *ROSAT* All-Sky Survey (Pfeffermann & Aschenbach 1996). The *ASCA* satellite, with wider energy coverage than that of *ROSAT*, revealed that the X-ray spectrum is featureless

¹ Department of High Energy Astrophysics, Institute of Space and Astronautical Science (ISAS), Japan Aerospace Exploration Agency (JAXA), 3-1-1 Yoshinodai, Sagami-cho, Kanagawa 229-8510, Japan

² Kavli Institute for Cosmology and Particle Astrophysics, Stanford Linear Accelerator Center, 2575 Sand Hill Road M/S 29, Menlo Park, CA 94025

³ Dublin Institute for Advanced Studies, 5 Merrion Square, Dublin 2, Ireland

⁴ Max-Planck-Institut für Kernphysik, PO Box 103980, 69029 Germany

⁵ Department of Physics, University of Tokyo, 7-3-1 Hongo, Bunkyo, Tokyo 113-0033, Japan

⁶ Cosmic Radiation Laboratory, RIKEN, 2-1 Hirosawa, Wako, Saitama 351-0198, Japan

⁷ Department of Physics, Tokyo Institute of Technology, Ohokayama, Meguro, Tokyo 152-8551, Japan

⁸ Department of Applied Physics, University of Miyazaki, 1-1 Gakuen Kibana-dai Nishi, Miyazaki 889-2192, Japan

⁹ X-ray Astrophysics Laboratory, NASA Goddard Space Flight Center, Greenbelt, MD 20771

and can be best interpreted as synchrotron emission from very high energy electrons in the TeV regime (Koyama et al. 1997; Slane et al. 1999). The X-ray spectrum was well fitted with a power-law function of photon index $\Gamma = 2.2$ – 2.4 and interstellar absorption column density $N_{\text{H}} = 0.6$ – $0.8 \times 10^{22} \text{ cm}^{-2}$ without any observable evidence for a thermal emission component. Subsequent observations by *Chandra* and *XMM-Newton* have unveiled structure with a complex network of bright filaments and knots, in the western part of the SNR (Uchiyama et al. 2003; Lazendic et al. 2004; Cassam-Chenaï et al. 2004; Hiraga et al. 2005).

TeV gamma-ray emission from RX J1713.7–3946 was first reported by the CANGAROO collaboration in 1998 (Muraishi et al. 2000), and confirmed by the subsequent observations with CANGAROO-II in 2000 and 2001 (Enomoto et al. 2002). Later, the H.E.S.S. collaboration obtained a resolved image of the source in TeV gamma rays (Aharonian et al. 2004) showing that the gamma-ray emission from RX J1713.7–3946 arises mainly in the shell. These observations revealed a striking correlation between the X-ray and the gamma-ray images, which indicates a strong connection between the physical processes responsible for X-ray and TeV gamma-ray emission components (Aharonian et al. 2006). Based on the spectral and morphological information, they discussed two possible gamma-ray emission scenarios, one where gamma rays are generated by inverse Compton scattering of accelerated electrons with diffuse radiation fields (the so-called leptonic scenario) and the other where the decay of secondary π^0 -mesons is responsible for gamma rays (hadronic scenario). The later observations with H.E.S.S. revealed that the flux extends to 30 TeV and, likely, beyond, which implies particle acceleration up to energies well above 100 TeV for either model (Aharonian et al. 2007).

Most recently, our X-ray observations using *Chandra* and *Suzaku* have provided important clues for understanding the acceleration process in the SNR. From a series of observations of the northwest part of the SNR with *Chandra* in 2000, 2005 and 2006, we discovered that compact regions of the northwest (NW) shell are variable in flux on a one-year time scale (Uchiyama et al. 2007). The fast variability was interpreted as one-year scale acceleration and synchrotron cooling of electrons with amplified magnetic fields of order of 1 mG. Such a large magnetic field in compact regions strongly favors π^0 -decay emission as the origin of TeV gamma rays. Also, thanks to the wide-band coverage of *Suzaku* and its low background level, we were able to measure a hard X-ray spectrum up to 40 keV from the southwest portion of RX J1713.7–3946 with a clear indication of a high-energy cutoff in the synchrotron spectrum (Takahashi et al. 2008, hereafter Paper I). Combined with the upper limit on a shock speed of 4500 km s^{-1} placed by *Chandra*, the cutoff energy determined by the *Suzaku* observation of the southwest part indicates that particle acceleration within the SNR shock is so efficient that it approaches the theoretical limit corresponding to the so-called Bohm diffusion regime (e.g. Malkov & Drury 2001).

In this paper, we present results of mapping observations of RX J1713.7–3946 with *Suzaku*, which covers about two-thirds of the SNR region with 11 pointings. The low background level of the Hard X-ray Detector (HXD) enables us to detect hard X-ray emission up to $\sim 40 \text{ keV}$ from each of the pointings. At the same time, its small field-of-view (FoV) of $\sim 25' \times 25'$ FWHM gives us information about the spatial distribution of hard X-ray emission and spectral differences from region to region. Thanks to its low instrumental

background and large effective area, the other detector system aboard *Suzaku*, the X-ray Imaging Spectrometer (XIS), also uncovers new observational facts, such as spectral features below 10 keV and the morphology of relatively dim regions left unclear in previous studies by *ASCA*, *Chandra*, and *XMM-Newton*. By combining the XIS and HXD spectra summed over the data from all the pointings, we show a wide-band X-ray spectrum (0.4–40 keV) with quite high statistics, with which we investigate not only the existence of a cutoff, but also its shape. We then compare the cutoff shape obtained with theoretical predictions.

In Section 2, we describe our *Suzaku* observations and the data reduction procedures. Analysis and results of HXD and XIS data are shown in §3.1 and §3.2, respectively. We present the wide-band spectrum by connecting the XIS and the HXD data in §3.3. A detailed study regarding the cutoff structure is also given there. Section 4 is devoted to multi-wavelength spectral and morphological studies. The results obtained are discussed in the following section, and the results are finally summarized. Throughout this paper, we assume that the distance to RX J1713.7–3946 is close to 1 kpc as proposed by Koyama et al. (1997) based on the N_{H} value. A similar distance has been claimed based on the NANTEN CO data (Fukui et al. 2003; Moriguchi et al. 2005). The typical age of the remnant for such a distance is estimated of order of 1000 yr, which can be an indication of association of RX J1713.7–3946 with an explosion in A.D. 393 as proposed by Wang et al. (1997).

2. SUZAKU OBSERVATIONS AND DATA REDUCTION

The *Suzaku* observatory (Mitsuda et al. 2007) is the fifth Japanese X-ray astronomy satellite, jointly developed by Japan and the US. Its scientific payload consists of two co-aligned detector systems, the XIS (Koyama et al. 2007) and the HXD (Takahashi et al. 2007; Kokubun et al. 2007). The XIS consists of four X-ray CCD cameras which are located in the foci of X-ray telescopes (XRT; Serlemitsos et al. 2007). Three of the XIS sensors are front-illuminated (FI; 0.4–12 keV) CCDs and the other is back-illuminated (BI 0.2–12 keV). The non-imaging, collimated hard X-ray instrument, the HXD, covers the 10–600 keV bandpass. Two main detector units, silicon PIN diodes and GSO scintillators, are buried at the bottom of well-type active shield of BGO. The former covers the lower energy band of 10–60 keV, while the latter detects higher energy photons of 40–600 keV.

We performed 11 pointing observations of RX J1713.7–3946 with *Suzaku*. The observation log is summarized in Table 1, and the pointing position of each observation is shown in Figure 1. The southwest part of the SNR, labeled as Pointing 0, was observed in 2005 during the Performance Verification phase, while the other ten observations were performed in 2006 during the *Suzaku* AO1 phase. Since the SNR is located on the Galactic plane, it is of importance to check the hard X-ray background associated with the Milky Way. We therefore observed two nearby background regions containing no bright X-ray point sources. The pointing positions of these “OFF” observations are shown with red squares in Figure 1. The XIS was operated in the normal full-frame clocking mode without spaced-row charge injection during all the observations. Since the results from Pointing 0, together with those from the OFF observations, are already reported in Paper I, we do not give a detailed description on the analysis and results for these data.

We used data products from the pipeline processing version




FIG. 1.— *Suzaku* FoV of each observation of the RX J1713.7–1713 region overlaid on the ASCA GIS image (1–5 keV) taken from Uchiyama et al. (2005). The small squares corresponds to the FoV of the XIS. the outer diamonds drawn for each “OFF” pointing is the rough shape of the FOV (50% of the effective area) of the HXD PIN. The numbers indicated in the XIS FoV are pointing IDs used throughout this paper.

1.2. For the XIS analysis, we retrieved “cleaned event files” which are screened using standard event selection criteria. For the 2006 data, we recalculated the values of pulse invariant (PI) and the grade values since incorrect CALDB is applied to the pipeline processing of these data as announced by the *Suzaku* instrument teams. We further screened the cleaned events with following criteria as recommended by the *Suzaku* instrument teams – (1) cut-off rigidity larger than 6 GV and (2) elevation angle from the Earth rim larger than 10° . For the HXD data, “uncleaned event files” were screened using standard event screening criteria. The exposure times after these screenings are shown in Table 1. Due to unstable operation of 16 PIN diodes installed in Well-counter units, W00–W03; hereafter W0, the bias voltage for these diodes was reduced to 400 V from the nominal voltage of 500 V on 26 May 2006. On 2006 October 4, the bias voltage of 16 more PIN diodes (the PIN diodes in the Well-counter units of W10–W13; W1) was reduced to 400 V for the same reason. The reduction of the PIN diode bias voltage leads to a decrease of their effective area and also affects their energy response. Since the current response matrices do not include these effects, only the PIN diodes with a bias voltage of 500 V are utilized in the following analysis. Throughout this paper, the data reduction and analysis are performed using HEADAS 6.2 and the spectral fitting is done with XSPEC 11.3.2.

3. ANALYSIS AND RESULTS

3.1. HXD Data Analysis

3.1.1. Spectral Analysis

The HXD PIN spectrum from each pointing was constructed and compared with the background model estimated for the each observation period. In the analysis below, the non-X-ray background (NXB) model (Watanabe et al. 2007) provided by the HXD team is used for the background generation. Since the NXB model does not include the contributions from the cosmic X-ray background (CXB), a simulated CXB

spectrum was added to the NXB model. Specifically, based on the reanalysis of the data from *HEAO-1* observations in the 1970’s (Gruber et al. 1999), the CXB spectrum was modeled as

$$\frac{dN}{d\varepsilon} = 7.9 \varepsilon_{\text{keV}}^{-1.29} \exp\left(-\frac{\varepsilon_{\text{keV}}}{\varepsilon_p}\right) \text{ ph s}^{-1} \text{ keV}^{-1} \text{ cm}^{-2} \text{ str}^{-1} \quad (1)$$

where $\varepsilon_{\text{keV}} = \varepsilon/1 \text{ keV}$ and $\varepsilon_p = 41.13$. We estimated the CXB signal in each HXD PIN spectrum using the response matrix for spatially uniform emission, `ae_hxd_pinflat_20060809.rsp`, `ae_hxd_pinflat123_20060809.rsp`, and `ae_hxd_pinflat23_20060809.rsp`. The contribution from the CXB flux to the detected count rate is estimated to be $\sim 5\%$ of the NXB.

Figure 2 shows the HXD PIN spectrum obtained from Pointing 8, where a clear detection of hard X-rays can be seen. Likewise, the HXD PIN detected signals from all other pointings with a count rate of 20–50% of the NXB. We fitted the background-subtracted spectra with a simple power law model: $dN/d\varepsilon \propto \varepsilon^{-\Gamma}$. Since the extended nature of the source does not cause any spectral steepening or flattening (Paper I), we used the point-source response matrix at the XIS-nominal position, `ae_hxd_pinxinom_20060814.rsp`, `ae_hxd_pinxinom123_20060814.rsp`, and `ae_hxd_pinxinom23_20060814.rsp`. Table 2 gives the best-fit parameters with the statistical errors at 90% confidence level. The obtained photon indices are generally larger than those obtained from the corresponding XIS spectra (see below). This difference indicates that a spectral cutoff is not unique to the SW region (Paper I), but a common feature throughout the remnant.

In order to confirm the results obtained above, we evaluated the systematic errors due to uncertainties in the NXB modeling. As described in Mizuno et al. (2006), the current reproducibility of the NXB model is $\sim 5\%$. Therefore, we examined how much the values of the photon index change by increasing or decreasing the background model by 5%. The systematic errors were found to be smaller than the statistical errors indicated in Table 2.

The systematic errors due to the misestimation of NXB were examined in another way. Considering the physical size of this target, the emission from the remnant should be constant during the observations. Therefore, background-subtracted lightcurves should be constant during a observation. Although the lightcurves shown are almost constant within statistical errors, the background-subtracted count rate becomes higher when the total count rate increases for Pointings 0 and 8. The light curves for Pointings 0 and 8 are shown in Paper I and Figure 3, respectively. Since this behavior is thought to be caused by misestimation of the NXB, we examined how much the photon indices change with and without those time regions. When we discard the time region which corresponds to the last bin of Figure 3, the photon index changes by $\Delta\Gamma \simeq 0.2$ from the values in Table 2.

Diffuse emission from the Galactic plane also can affect the spectra. However, no emission above the 5% level of the NXB was detected from the OFF pointings (Paper I). Moreover, when the excess counts marginally detected from the OFF pointings are added to the background spectrum for each pointing, the fitting result agrees within the statistical errors.

3.1.2. Spatial Distribution of Hard X-ray Emission

TABLE 1
SUMMARY OF THE *Suzaku* OBSERVATIONS OF RX J1713.7–3946

Pointing ID	Obs. ID	Coord. (J2000) (α_{J2000} , δ_{J2000})	Exposure XIS/HXD [ks]	Date
0	100026010	(17 ^h 12 ^m 17 ^s .0, −39 ^d 56 ^m 11 ^s)	55/48	26/9/2005
1	501063010	(17 ^h 11 ^m 51 ^s .5, −39 ^d 31 ^m 13 ^s)	17/17	11/9/2006
2	501064010	(17 ^h 12 ^m 38 ^s .0, −39 ^d 40 ^m 14 ^s)	18/22	11/9/2006
3	501065010	(17 ^h 12 ^m 38 ^s .2, −39 ^d 22 ^m 15 ^s)	19/18	11/9/2006
4	501066010	(17 ^h 11 ^m 04 ^s .5, −39 ^d 40 ^m 10 ^s)	19/21	12/9/2006
5	501067010	(17 ^h 11 ^m 05 ^s .1, −39 ^d 22 ^m 10 ^s)	16/19	12/9/2006
6	501068010	(17 ^h 14 ^m 11 ^s .6, −39 ^d 40 ^m 14 ^s)	20/19	13/9/2006
7	501069010	(17 ^h 14 ^m 11 ^s .4, −39 ^d 22 ^m 15 ^s)	12/11	19/9/2006
8	501070010	(17 ^h 14 ^m 11 ^s .8, −39 ^d 58 ^m 14 ^s)	19/20	19/9/2006
9	501071010	(17 ^h 12 ^m 17 ^s .6, −39 ^d 18 ^m 50 ^s)	16/15	20/9/2006
10	501072010	(17 ^h 15 ^m 44 ^s .5, −39 ^d 40 ^m 10 ^s)	15/15	5/10/2006
OFF1	100026020	(17 ^h 09 ^m 31 ^s .9, −38 ^d 49 ^m 24 ^s)	28/24	25/9/2005
OFF2	100026030	(17 ^h 09 ^m 05 ^s .1, −41 ^d 02 ^m 07 ^s)	30/28	28/9/2005

TABLE 2
POWER-LAW FITTING TO THE HXD PIN SPECTRA^a

Pointing ID	Γ	$F_{10-40 \text{ keV}}$ (mCrab)	χ^2_ν (ν)	Used Units
0	3.2 ± 0.2	2.5 ± 0.1	1.15 (36)	W0–3
1	3.3 ± 0.2	3.2 ± 0.2	0.91 (18)	W1–3
2	3.0 ± 0.3	3.2 ± 0.2	0.84 (21)	W1–3
3	3.4 ± 0.5	2.0 ± 0.2	0.58 (17)	W1–3
4	2.9 ± 0.3	3.5 ± 0.2	0.77 (23)	W1–3
5	3.2 ± 0.5	1.7 ± 0.2	0.76 (17)	W1–3
6	2.9 ± 0.3	2.9 ± 0.2	0.72 (20)	W1–3
7	$3.9^{+1.4}_{-1.1}$	$1.2^{+0.3}_{-0.2}$	0.42 (9)	W1–3
8	$2.6^{+0.5}_{-0.4}$	2.2 ± 0.2	0.87 (19)	W1–3
9	$3.0^{+1.2}_{-1.0}$	1.1 ± 0.2	0.86 (12)	W1–3
10	$4.4^{+1.0}_{-1.2}$	1.0 ± 0.2	0.20 (8)	W2, 3

^a Errors represent 90% confidence.




FIG. 2.— The HXD PIN spectrum obtained from the observation of Pointing 8. The data points in black show the raw spectrum, red points represent the background model (NXB+CXB), and green points are the background-subtracted spectrum.

Using the spectral parameters obtained for the 11, pointings we attempt to reconstruct the spatial distribution of the hard X-ray emission. Since we expect spatial variation of both brightness and spectral index, we use a Monte Carlo simulator, *simHXD* (Terada et al. 2005), for the estimation. We input the spatial distribution of brightness and spectral index into *simHXD*, and compare the simulated spectra with observed ones shown in §3.1.1.




FIG. 3.— The HXD PIN light curve during the observation of Pointing 8. Events with energy from 12 keV to 40 keV are selected. The black, red, and green points show the raw, background (NXB), and background-subtracted data, respectively.

Firstly we simulated by taking a simple model in which the brightness distribution is same as the *ASCA* image shown in Figure 4 and the spectral index is constant at $\Gamma = 3.0$ throughout the SNR (*simulation1*). By using the *ASCA* image as an input to *simHXD*, we simulated hard X-ray spectra in 10–40 keV, which are expected to be observed by the PIN in each pointing. Figure 5 compares the flux from the observations and the simulations. In this figure, each value is normalized to that of Pointing 0. Here, the systematic error for each observational data point is $\sim 20\%$ if we use the 5% of the back-




FIG. 4.— The emission distribution (left) and the photon index distribution (right) adopted in the simulations. The emission distribution is the ASCA image in the energy range of 1–5 keV.

ground as systematic errors. The observations and the simulations appear consistent with each other. Therefore, we expect the brightness distribution above 10 keV is not drastically different from the distribution below 10 keV.

The largest discrepancy between the observation and the simulation is found for Pointing 4. In this pointing, there is a known point source at the corner of the HXD-PIN field of view. The source is listed in the Second IBIS/ISGRI Soft Gamma-Ray Survey Catalog (Bird et al. 2006) as IGR J17088–4008. According to Bird et al. (2006), the average flux of this source is 1.1 ± 0.2 mCrab in 20–40 keV and 2.2 ± 0.3 mCrab in 40–100 keV. It is noted that the source is not bright enough for IBIS/ISGRI to determine spectral parameters. The transmission of fine collimators of the HXD for the source is estimated to be ~ 0.05 . The estimated count rate of this source corresponds to $\sim 2\%$ of the detected signals from Pointing 4. However, the variability of this source could increase the count rate to a non-negligible level. The observation and the simulation become consistent if the point source was 10 times brighter than its average value during the *Suzaku* observation. Also, the angular response of the HXD near the edge of the FoV can have some uncertainties since calibrations for a source with such a large offset angle is difficult. The uncertainties can affect our estimate of the contamination from IGR J17088–4008. At this moment, we cannot conclude that the large difference between the observation and the simulation is due to the spatial distribution of the SNR emission or the point source in the FoV.

Next we tried another simulation taking into account the spatial distribution of spectral indices (*simulation2*). We adopt a “toy model” shown in Figure 4 since the results of the spectral analysis presented in Table 2 suggest that the hard X-ray spectrum may be flatter in the inner region of the SNR than near the rim. In the model, the photon index of the inner region is set to $\Gamma = 2.6$ and that of the rim region is set to $\Gamma = 3.5$. The ASCA image was used to provide the brightness distribution at 10 keV.

Comparisons of the data and the simulation results are shown in Figure 5 and Figure 6 for the flux and photon index, respectively. The detected flux obtained from *simulation2* is somewhat similar to that from *simulation1*, and the simulation data generally follow the observational data. As for the distribution of photon indices, the toy model gives a similar distribution to the observational results for the western portion of the SNR. Obtaining a better fit for the eastern region (Pointing 7, 8, and 10) may require more complex assumptions than the toy model for *simulation2*.

3.2. XIS Data Analysis

3.2.1. Image Analysis




FIG. 5.— Comparison of detected flux obtained from the observations, *simulation1*, and *simulation2*. Each data point is normalized to the value of Pointing 0. The error bars indicate 1σ statistical errors.




FIG. 6.— Comparison of photon indices obtained from the observations and *simulation2*. The error bars correspond to 1σ statistical errors.

Figure 7 shows mosaic images of RX J1713.7–3946, constructed using the data from XIS0, 2, and 3 (FI-CCDs). The upper panel shows the soft band image in 1–5 keV and the lower panel shows the hard band image in 5–10 keV. Both images are smoothed with a Gaussian of $\sigma = 0''.3$. Instrumental background signals are subtracted from both images. The signal to background ratio in the hard band is smaller than that in the soft band by one order of magnitude. Thus, the background must be carefully subtracted. We utilized the Night Earth Background Database consisting of event data obtained when the satellite is looking at the night earth and the non X-ray background becomes dominant. After subtracting the background, the vignetting effects of the XRTs were corrected by means of the simulation program called *xissim* (Ishisaki et al. 2007). In the program, an image from a flat field can be simulated by a Monte Carlo method.

As is seen in Figure 7, the *Suzaku* XIS has covered most of the remnant. Thanks to little stray-light contamination of the XRTs and low background level of the XIS, high quality images are obtained even in the high energy band above 5 keV. The double shell structure revealed by *XMM-Newton* is clearly seen in the XIS images. In addition to the bright structures of the western part, the XIS revealed detailed morphology of the dim parts of the remnant. The dim structures are highlighted in Figure 8, which is the same as Figure 7 (a) but displayed with a different color scale. In this figure, the contours of the H.E.S.S. gamma-ray image (from Aharonian et al.

2007) are overlaid for comparison. As is clearly seen, not only the bright rims but also the eastern portion shows a striking similarity between the two energy regimes. This correlation is discussed more quantitatively in §3.4.

Two point sources seen in the soft band image are listed in the *ROSAT* bright source catalogue. One is 1WGA J1714.4–3945, which was associated with a Wolf-Rayet star by Pfeffermann & Aschenbach (1996). The other is 1WGA J1713.4–3949, which is located between the two FoVs of Pointing 2 and 6. This source has been suggested to be the neutron star associated with the SNR by Lazendic et al. (2003).

Comparing the soft-band and hard-band images provides information about the spatial variations of the spectral properties. At first sight, the bright structures are very similar in the soft band and hard band images. In order to compare the images in more detail, a radial profile around the center of SNR ($\alpha_{J2000} = 17^h13^m33^s.6$, $\delta_{J2000} = -39^\circ45'36''$) is presented in Figure 9, where circular regions of $2'.1$ radius centered on the two point sources are excluded. The hard band to soft band ratio is significantly different between the bright outer region part and the interior. This difference suggests a corresponding difference in spectral properties.

3.2.2. Spectral Analysis

As already reported in Paper I, the XIS data reveal a cutoff below 10 keV in the spectrum of the SW rim. The XIS spectra from the various regions should reveal whether the cutoff varies across the remnant. We extracted spectra from the regions shown in Figure 7 with the green squares. The region labeled as “1” (Region 1) is the same one that we used for the spectral analysis in Paper I. The background spectrum needs to be accumulated from nearby regions since RX J1713.7–3946 is located almost on the Galactic plane. The OFF observation data cannot be used for background estimation other than for Region 1. This is because the contamination on the optical blocking filters of the XIS (Koyama et al. 2007) significantly changed the detector response to low-energy X-rays between 2005 and 2006. For Region 1–10 we therefore accumulated a background spectrum from the regions indicated with the magenta polygons in Figure 7. In the spectral fitting discussed below, the standard RMF files version 2006-02-13 were used, whereas ARF files were produced using *xissimarfgen*. Each spectrum is binned so that each bin contains at least 300 counts. After the binning, we ignore those bins whose energy is smaller than 0.4 keV or larger than 12 keV. We also excluded bins between 1.7 and 1.9 keV because there exist large systematic uncertainties in the response matrices. Finally, we co-added the spectra, RMF files, and ARF files from the FI chips to produce a single data set for the XIS.

First, we fitted all the spectra with a simple power law absorbed by the interstellar medium. The results are summarized in Table 3. This model yields acceptable fits for most of the spectra. However, the fits to the spectra of Region 1, 2, and 6 are not acceptable even at the 99% confidence level. We show the spectrum of Region 2 with the best-fit power-law and the residuals in Figure 10. Although not so drastic as Region 1 which is shown in Paper I, a correlated pattern to the residuals can be seen for the Region 2. A similar pattern is also seen in the data of Region 6.

We fitted all the spectra with a cutoff power law. This function gives acceptable fits for all regions, and consistently gives better values of χ^2_ν . In Figure 10, we plot the residuals




FIG. 7.— The XIS (XIS 0+2+3) mosaic images of RX J1713.7–3946 in the energy band 1–5 keV (a) and 5–10 keV (b). North is up and east is to the left. The color scale indicates count rate on a linear scale. The green regions in the top panel are those used for spectral analysis. The dashed magenta polygons correspond to the regions used to extract the background spectrum. The positions of the two point sources, 1WGA J1714.4–3945 and 1WGA J1713.4–3949 are shown with white circles. The dashed green circles represent radii of 0.3° and 0.6° around the center of the SNR ($\alpha_{J2000} = 17^h13^m33^s.6$, $\delta_{J2000} = -39^\circ45'36''$), which correspond to the vertical dashed lines in Figure 9.

for the spectrum of Region 2. These results, together with the steeper spectra detected with HXD, indicate the existence of a cutoff somewhere between the bandpasses of the XIS and HXD.

Although statistically rejected for some regions, the results obtained with the power-law fits are consistent with previous studies with *ASCA*, *Chandra*, and *XMM-Newton* (Koyama et al. 1997; Slane et al. 1999; Uchiyama et al. 2003; Cassam-Chenaï et al. 2004; Hiraga et al. 2005). The results with *Suzaku* suggest that the photon index is larger and the absorption is smaller for the inner regions than for the outer regions. This tendency agrees with the radial profile shown in Figure 9. The difference of N_H between the western bright spots and the inner region is $\Delta N_H \simeq 0.3\text{--}0.4 \times 10^{22} \text{ cm}^{-2}$, which is consistent with the results from *XMM-Newton*. According to the discussion by Hiraga et al. (2005), there could




FIG. 8.— Comparison of the *Suzaku* XIS image and the gamma-ray image by the H.E.S.S. telescope (contours) taken from Aharonian et al. (2007) shown with color scale and green contours, respectively. The XIS image is same as Figure 7 (a) but the scale is changed to stress the similarity of the two images.




FIG. 9.— Radial profiles around the center of the SNR ($\alpha_{J2000} = 17^h13^m33.6^s$, $\delta_{J2000} = -39^\circ45'36''$) in the two energy bands. Each profile is normalized to its peak value for direct comparison. The radii corresponding to the vertical dashed lines are shown in Figure 7 (b) with the green dashed circles.

be a correlation between the difference of N_H and the presence of the molecular clouds in the western part of the SNR detected with the NANTEN telescope (Fukui et al. 2003; Moriguchi et al. 2005).

3.3. Broad-Band X-Ray Spectral Analysis

In this section, we connect the XIS and HXD spectra, which is crucial for a quantitative study of the cutoff structure and also for multi-wavelength study described in §3.4. In order to study the general characteristics of the emission from RX J1713.7–3946, the XIS and HXD spectra obtained in §3.2/§3.1 were co-added. Then, the summed XIS and HXD spectra were scaled to account for the flux from the whole remnant, which makes it easier not only to connect the XIS and HXD spectra but also to compare the combined spectrum directly to those of other wavelengths in §3.4. In scaling the spectra to the whole remnant, we assumed the surface brightness of the ASCA GIS image (1–5 keV) shown in Figure 1, the angular response of the XIS/XRT system (ARFs), and that




FIG. 10.— The XIS (XIS 0+2+3) spectrum from Region 2. The lower panels show the residuals when the spectrum is fitted with a power law and a power law with an exponential cutoff.

of the HXD PIN presented in Figure 6 of Paper I. The relative normalization factor between XIS and HXD derived from Crab observations (Ishida et al. 2006) is included in the scaling. Therefore, the scaled XIS and HXD can be connected to each other without additional scaling if no systematic errors are considered. However, we estimate that the normalization of the XIS and HXD spectra obtained by the procedures above should contain systematic errors of 10–20%. In order to account for the systematic errors, we include a constant normalization factor and deal with this factor as a free parameter when fitting the XIS+HXD spectrum below. In this procedure, we discarded the HXD data from Pointing 4 since they seem to be contaminated by a nearby hard X-ray source as described in §3.1.2.

Before the XIS and HXD spectra were jointly analyzed, each co-added spectrum was independently fitted using a power-law function. Table 4 summarizes the fit results. The HXD spectrum gives an acceptable fit. In contrast, the XIS does not, with a large chi-squared value of $\chi_\nu^2 = 1.57$ for 711 degrees of freedom and residuals that begin to become large at ~ 6 keV. This fact is clearly seen in Figure 11, where the XIS and HXD spectra are plotted together with a power-law function which represents the XIS spectrum. The spectral steepening begins in the XIS band and continues smoothly into the HXD band. This plot strongly suggests that spectral steepening occurs around 10 keV. We have already reported such a spectral feature in Paper I for Pointing 0 data. The same kind of feature has been revealed in this spectrum averaged over the SNR, which suggests that the spectral steepening is common in the entire region.

We then quantitatively evaluated the spectral steepening by fitting a model with a cutoff structure to the combined XIS/HXD spectrum. Below we use our numerically calculated synchrotron spectrum which was embedded into the XSPEC package. As an electron distribution, we adopt a generalized form, namely,

$$\frac{dN_e}{dE} \propto E^{-s} \exp \left[- \left(\frac{E}{E_0} \right)^\beta \right], \quad (2)$$

instead of taking a simple *exponential cutoff* often used in the literature. Here, s represents index of electron spectrum and $\beta (> 0)$ determines rapidity of high-energy cutoff. The photon

TABLE 3
MODEL FITTING TO THE XIS SPECTRA^a

Region	Area (arcmin ²)	Power law				Cutoff power law				
		N_H (10 ²² cm ⁻²)	Γ	$F_{1-10 \text{ keV}}^b$ (10 ⁻¹¹ erg s ⁻¹ cm ⁻²)	$\chi\nu^2(\nu)$	N_H (10 ²² cm ⁻²)	Γ	ε_c (keV)	$F_{1-10 \text{ keV}}^b$ (10 ⁻¹¹ erg s ⁻¹ cm ⁻²)	$\chi\nu^2(\nu)$
1	108	0.87 ± 0.01	2.39 ± 0.01	6.06 ± 0.03	1.38 (718)	0.77 ± 0.01	1.96 ± 0.05	9 ± 1	5.7 ± 0.1	1.04 (717)
2	77.2	0.83 ± 0.02	2.38 ± 0.02	5.22 ± 0.05	1.23 (242)	0.73 ± 0.03	2.00 ± 0.09	10 ⁺³ ₋₂	4.9 ± 0.2	1.01 (241)
3	86.6	0.55 ± 0.03	2.62 ± 0.04	1.41 ± 0.03	1.14 (94)	0.47 ± 0.04	2.2 ± 0.2	8 ⁺⁷ ₋₃	1.3 ± 0.1	1.02 (93)
4	42.2	0.54 ± 0.04	2.72 ± 0.07	0.66 ± 0.02	1.38 (44)	0.44 ± 0.07	2.2 ± 0.3	6 ⁺⁸ ₋₂	0.60 ^{+0.06} _{-0.05}	1.23 (43)
5	116	0.78 ± 0.03	2.39 ± 0.04	1.88 ± 0.04	1.18 (120)	0.70 ± 0.05	2.1 ± 0.2	11 ⁺¹³ ₋₄	1.8 ± 0.1	1.12 (119)
6	51.4	0.88 ^{+0.06} _{-0.05}	2.43 ± 0.06	1.27 ± 0.04	1.63 (48)	0.68 ± 0.09	1.7 ± 0.3	5 ⁺³ ₋₂	1.1 ^{+0.2} _{-0.1}	1.24 (47)
7	59.6	0.71 ± 0.04	2.38 ± 0.05	1.18 ± 0.03	1.15 (56)	0.62 ± 0.07	2.0 ± 0.2	10 ⁺¹⁴ ₋₄	1.1 ± 0.1	1.03 (55)
8	72.4	0.78 ± 0.03	2.55 ± 0.04	1.91 ± 0.04	1.10 (110)	0.68 ± 0.05	2.1 ± 0.2	8 ⁺⁵ ₋₂	1.8 ± 0.1	0.92 (109)
9	65.9	0.81 ± 0.03	2.49 ^{+0.04} _{-0.03}	2.03 ± 0.04	1.11 (109)	0.74 ^{+0.04} _{-0.05}	2.2 ± 0.2	14 ⁺¹⁶ ₋₅	1.9 ^{+0.2} _{-0.1}	1.03 (108)
10	54.0	0.60 ± 0.04	2.23 ± 0.05	1.49 ± 0.03	0.88 (75)	0.52 ± 0.06	1.9 ± 0.2	12 ⁺¹⁹ ₋₅	1.4 ± 0.1	0.79 (74)

^a Errors represent 90% confidence. ^b Corrected for absorption.

spectrum can be calculated as

$$\frac{dN}{d\varepsilon} \propto \varepsilon^{-1} \int F \left(\frac{\varepsilon}{\varepsilon_c} \right) \frac{dN_e}{dE} dE. \quad (3)$$

Here the function $F(x)$ is defined as

$$F(x) \equiv x \int_x^\infty K_{5/3}(\xi) d\xi, \quad (4)$$

where $K_{5/3}$ is the modified Bessel function of 5/3 order. When pitch angles are isotropic, the characteristic photon energy ε_c is given as

$$\varepsilon_c = 0.543 \left(\frac{B}{100 \mu\text{G}} \right) \left(\frac{E}{10 \text{ TeV}} \right)^2 \text{ keV}. \quad (5)$$

The model consists of four parameters: s , $\Pi \equiv E_0 B^{1/2}$, β , and the flux normalization. Photon spectra were calculated and tabulated for reasonable ranges of the four parameters, to be used as an XSPEC table model. The parameters characterizing the electron energy distribution can be obtained directly from the fit to the X-ray data.

For RX J1713.7–3946, the most probable value for s is 3.0 rather than 2.0 due to significant synchrotron cooling of electrons during the lifetime of the SNR t_0 (~ 1000 yr). The electron spectrum becomes steeper by a factor of 1 ($s \rightarrow s+1$), when the injection of electrons is constant and the lifetime t_0 is smaller than the time scale of synchrotron cooling t_{sync} . Since t_{sync} can be written as

$$t_{\text{sync}} = 28 \left(\frac{B}{100 \mu\text{G}} \right)^{-3/2} \left(\frac{\varepsilon}{3 \text{ keV}} \right)^{-1/2} \text{ yr}, \quad (6)$$

the condition above is satisfied in the energy range,

$$\varepsilon > \varepsilon_b \equiv 2.3 \left(\frac{B}{100 \mu\text{G}} \right)^{-3} \left(\frac{t_0}{10^3 \text{ yr}} \right)^{-2} \text{ eV}. \quad (7)$$

To explain the variability of X-ray emission reported on a year timescale from compact regions of the shell of RX J1713.7–3946, Uchiyama et al. (2007) proposed that the magnetic field in these compact regions is amplified to 1 mG. The average large-scale magnetic field in the remnant should be significantly lower, but even for $B \simeq 100 \mu\text{G}$ the above condition in the X-ray domain is safely satisfied. Therefore, for a strong shock with a compression ratio of 4.0, the index of X-ray emitting electrons should be close to $s = 3.0$.

We fitted the *Suzaku* spectrum with the synchrotron spectrum described above. In the fitting procedure, we fixed the

electron index s . Table 5 summarizes the result in the case of $s = 3.0$, which corresponds to the most probable case following the discussion above. We also present results when $s = 2.0$ for comparison. This case can be realized if the magnetic field and/or the age of the remnant are much smaller than we expect, as is seen in equation (7). The spectral fitting with the electron index of $s = 3.0$ yields rather rapid steepening with $\beta = 3.4^{+0.7}_{-0.5}$ compared to the conventionally used *exponential cutoff*. However, one should be careful with the physical interpretation of the fit based on equation (2). Indeed, while the electron spectrum is derived from the broad-band *Suzaku* X-ray data assuming a specific spectral form given by equation (2), the curve 1 in Figure 12 has a more general meaning. It does not depend on the assumed analytical presentation and, in fact, relates *uniquely* the energy spectrum of electrons to the measured X-ray spectrum. Indeed, the curve 1 can be presented in different mathematical forms. In particular, the electron spectrum shown by curve 1 in Figure 12 is quite close to the theoretical prediction for the spectrum of shock accelerated electrons in a young SNR (Zirakashvili & Aharonian 2007),

$$\frac{dN_e}{dE} \propto E^{-3} \left[1 + 0.66 \left(\frac{E}{E_0} \right)^{5/2} \right]^{9/5} \exp \left[- \left(\frac{E}{E_0} \right)^2 \right]. \quad (8)$$

This spectrum is derived under the assumption that electrons are accelerated by a strong shock in the Bohm diffusion regime and that the energy losses of electrons are dominated by synchrotron cooling. It is seen that the energy spectrum below the cutoff is described by a function which deviates from a pure power-law form, by an exponential term with $\beta = 2$. The latter has a simple physical interpretation and is a result of combination of two effects — acceleration in the Bohm diffusion regime, and energy losses in the synchrotron regime. The curve 2 shown in Figure 12 is calculated for the parameter $\Pi = E_0 B^{1/2} = 201 \text{ TeV } \mu\text{G}^{1/2}$.

The energy spectrum of synchrotron radiation corresponding to the electron spectrum given by equation (8) has a form (Zirakashvili & Aharonian 2007)

$$\frac{dN}{d\varepsilon} \propto \varepsilon^{-2} \left[1 + 0.46 \left(\frac{\varepsilon}{\varepsilon_0} \right)^{0.67} \right]^{2.29} \exp \left[- \left(\frac{\varepsilon}{\varepsilon_0} \right)^{1/2} \right]. \quad (9)$$

This spectrum fits well the broad-band *Suzaku* X-ray data for a single parameter $\varepsilon_0 = 0.67 \pm 0.02 \text{ keV}$. Note that the exponential term in the synchrotron spectrum is a weak function




FIG. 11.— The *Suzaku* (XIS+HXD) spectrum of RX J1713.7–3946. The model plotted with the data is a power law obtained by fitting the XIS data. The parameters are shown in Table 4. The lower panel shows the ratio of the data to the model, and clearly reveals a cutoff.




FIG. 12.— Comparison of electron spectra in the high-energy cutoff region. Curve 1 is the electron spectrum obtained by fitting the *Suzaku* spectrum with a synchrotron spectrum assuming the electron distribution given by equation 2 when s is fixed to 3.0. Curve 2 is the model by Zirakashvili & Aharonian (2007). Both the spectra are drawn by assuming the best-fit parameters of the *Suzaku* spectrum, which are shown in Table 5. Curve 3 is the *exponential cutoff* spectrum often assumed in the literature. The cutoff energy is set to the same value as that of curve 1.

of energy ($\propto \exp[-(\varepsilon/\varepsilon_0)^{1/2}]$); therefore the characteristic energy ε_0 only formally can be considered as the cutoff energy. In fact, for the shape given by equation (9), the break in the spectrum starts at much higher energies ($\varepsilon \sim 10\varepsilon_0$).

3.4. Multi-Wavelength Study

3.4.1. Spectral Energy Distribution

The high quality data of *Suzaku* obtained over two decades in energy and combined with the TeV gamma ray data, allow definite conclusions concerning the origin of multi-TeV parent particles based on the comparison of model predictions with observations. In particular it is important that the *Suzaku* data provide unambiguous information about the shape of the energy spectrum of electrons in the cutoff region.

Figure 13 shows the Spectral Energy Distribution (SED), $E^2 dN/dE$, of RX J1713.7–3946 from radio to TeV energies. The X-ray data correspond to the entire remnant; they are reconstructed assuming the best-fit model given by equation (9) corrected for the interstellar absorption with $N_H = 0.70 \times 10^{22} \text{ cm}^{-2}$. The points in the TeV gamma-ray range corresponding to the fluxes of the whole remnant, are from the latest report of the H.E.S.S. collaboration (Aharonian et al. 2007). The EGRET upper limit is taken from Aharonian et al. (2006); it is obtained through modeling and subtracting

the resolved EGRET source 3EG 1714–3857 (Hartman et al. 1999). The two data points in the radio band are shown as measured with the ATCA telescope (Lazendic et al. 2004). But it should be noted that these fluxes are detected only from the NW rim region, therefore they should be treated as lower limits when compared to model predictions for the whole remnant. The recent estimates based on observations with ATCA and the 30-m radiotelescope IRA show that the flux of the entire remnant should be a factor of few larger than the flux of the NW rim (F. Acero et al. 2008, in preparation; G. Dubner 2008, private communications).

In Figure 13 we show theoretical fluxes of broad-band electromagnetic radiation produced by both accelerated electrons and protons. The results depend strongly on the strength of the average magnetic field B . Although the magnetic field in compact filaments can be as large as $\sim 1 \text{ mG}$ (Uchiyama et al. 2007), the field in less bright and more diffuse regions where the bulk of the synchrotron X-ray emission is produced, should be significantly weaker. Yet, a moderately large field exceeding $100 \mu\text{G}$ is required to explain the X-ray flux ratio between the diffuse and compact zones. The integrated X-ray flux from the diffuse zone (zone 1) is larger by a factor of ~ 4 than that from the compact zone (zone 2): $F_1 \sim 4F_2$ (Uchiyama et al. 2003). Using the ratio of the emission volumes estimated from the X-ray image ($V_1 \sim 1000V_2$), the number density of X-ray emitting electrons, $n \propto F/(VB^2)$, in the zone 2 relative to the zone 1 is estimated as $n_2 \sim 250(B_1/B_2)^2 n_1$. For $B \gtrsim 1 \text{ mG}$, and assuming $n_2 \geq n_1$, one finds $B_1 \geq 100 \mu\text{G}$.

In Figure 13 the synchrotron, inverse Compton (IC), and π^0 -decay fluxes are calculated assuming strong uniform magnetic field of strength $B = 200 \mu\text{G}$. The calculations are performed with constant injection of electrons and protons over the last 1000 yr. The injection spectrum for both electrons and protons is assumed to be a power-law with an index $s = 2.0$. For calculations of IC fluxes we used the diffuse photon fields proposed by Porter et al. (2006), including 2.7 K CMB, as well as interstellar radiation consisting of two, optical (starlight) and infrared (dust) emission components.

The best fits for the synchrotron radiation and π^0 -decay gamma rays are achieved for cutoffs in the energy distributions of electrons and protons at 28.4 TeV and 130 TeV, respectively. The spectra of π^0 -decay gamma rays are calculated using the analytical presentations by Kelner et al. (2007). Since the highest energy tail of the observed gamma-ray spectrum is best fitted with $\exp[-(\varepsilon/\varepsilon_0)^{\beta_\gamma}]$ with $\beta_\gamma \approx 0.5$ (Aharonian et al. 2007), the proton spectrum in the cutoff region should have an exponential behavior, $\beta_p \approx 2 \times \beta_\gamma = 1$ (see Kelner et al. 2007).

The electrons suffer synchrotron losses, thus the electron spectrum above a certain energy becomes steeper ($E^{-s} \rightarrow E^{-(s+1)}$). The position of the break in the electron spectrum appears at

$$E_b = 1.25 \left(\frac{B}{100 \mu\text{G}} \right)^{-2} \left(\frac{t_0}{10^3 \text{ yr}} \right)^{-1} \text{ TeV}. \quad (10)$$

For a magnetic field $B = 200 \mu\text{G}$ and age of the source $T \leq 1000 \text{ yr}$, the spectral break in the synchrotron spectrum corresponding to the transition of the electrons spectrum from uncooled to cooled regime, appears around 1 eV (see Figure 13). Thus, for young SNRs the detection of the synchrotron break at optical/infrared wavelengths would be an additional argument in favor of strong magnetic field. The cooling break in the electron spectrum is reflected also in the

TABLE 4
POWER-LAW FITTING TO THE XIS/HXD SPECTRUM OF THE WHOLE REMNANT^a

Detector	N_H (10^{22} cm^{-2})	Γ	Flux ^b ($10^{-10} \text{ erg s}^{-1} \text{ cm}^{-2}$)	$\chi_\nu^2 (\nu)$
XIS (0.4–12 keV)	0.79 ± 0.01	2.39 ± 0.01	7.65 ± 0.03	1.57 (711)
HXD (12–40 keV)	—	3.2 ± 0.1	1.17 ± 0.03	1.16 (67)

^a Errors represent 90% confidence. ^b Corrected for absorption. The calculated energy band is 1–10 keV and 10–40 keV for XIS and HXD, respectively.

TABLE 5
FITTING TO THE *Suzaku* (XIS+HXD) SPECTRUM^a

Assumed Function	N_H (10^{22} cm^{-2})	Constant Factor	Parameter(s)	$F_{1-10 \text{ keV}}^a$ ($10^{-10} \text{ erg s}^{-1} \text{ cm}^{-2}$)	$\chi_\nu^2 (\nu)$
Electron Distribution	0.71 ± 0.01	1.03 ± 0.06	$s = 3.0$ (fixed), $\beta = 3.4^{+0.7}_{-0.5}$, $\Pi = 402 \pm 6 \text{ TeV } \mu\text{G}^{1/2}$	7.2 ± 0.1	1.11 (778)
of Equation (2) ^c	0.68 ± 0.01	$1.03^{+0.06}_{-0.05}$	$s = 2.0$ (fixed), $\beta = 1.5 \pm 0.2$, $\Pi = 207^{+21}_{-20} \text{ TeV } \mu\text{G}^{1/2}$	7.1 ± 0.1	1.07 (778)
Z&A (2007) ^d	0.70 ± 0.01	1.08 ± 0.04	$\varepsilon_0 = 0.67 \pm 0.02 \text{ keV}$	7.2 ± 0.1	1.11 (779)

^a Errors represent 90% confidence. ^b Corrected for absorption. ^c Details of the calculation of synchrotron spectrum is described in the text. ^d A model by Zirakashvili & Aharonian (2007), the synchrotron spectrum of which is shown as equation (9) in this paper

gamma-ray band. Namely, for $B = 200 \mu\text{G}$ the corresponding signature in the IC gamma-ray spectrum appears around 10 GeV. Unfortunately (see Figure 13), for such a strong magnetic field, the IC component is suppressed, and falls well below the sensitivity of gamma-ray detectors in this energy band, including *GLAST*. At the presence of such a strong magnetic field, the only viable mechanism which can produce TeV gamma-rays at the flux level detected by H.E.S.S. is related to interactions of ultrarelativistic protons with ambient gas through production and decay of π^0 -mesons. To explain the detected flux of gamma-rays protons should be accelerated to energies well beyond 100 TeV, and the parameter $A = (W_p / 10^{50} \text{ erg})(n / 1 \text{ cm}^{-3})(d / 1 \text{ kpc})^{-2}$ should be between 1.5–3, depending on the spectrum of protons.

In order to increase the IC flux to the level of the observed TeV gamma-ray flux, the magnetic field should be reduced down to 10 μG and 15 μG . For the given magnetic field, the high quality X-ray data of *Suzaku* obtained over two energy decades allow derivation of the electron spectrum with high accuracy within the interval covering one energy decade: from $\sim 50(B/10 \mu\text{G})^{-1/2} \text{ TeV}$ to $\sim 500(B/10 \mu\text{G})^{-1/2} \text{ TeV}$. This allows us to calculate the spectrum and absolute flux of IC gamma rays above a few TeV without any model assumptions, as long as the main target for the IC gamma-ray production remains the 2.7 K CMB. The contribution of the diffuse optical/infrared radiation fields generally is less, however the optical photons may provide enhanced TeV emission at low, sub-TeV energies. For calculations of the IC spectrum we used the interstellar radiation model of Porter et al. (2006), who proposed significantly larger flux of optical and infrared components compared to the generally accepted flux. However, the results presented in Figure 14 show that even this high diffuse optical and infrared radiation fails to account for the observed gamma-ray flux below a few TeV. In order to fill this gap one needs to assume an unreasonably large density of optical radiation. This is demonstrated in Figure 15, where an agreement of IC calculations with the reported gamma-ray fluxes is achieved assuming an additional, although in our view quite unrealistic, component of optical radiation with a density of 140 eV cm^{-3} .

It should be noted that the problem of explanation of low energy gamma rays in Figure 14 is related to the large en-

ergy of the break in the electron spectrum given by equation (10), and correspondingly to the position of the Compton peak which appears above 1 TeV in the spectral energy distribution of gamma rays. Thus, the reduction of the break energy down to 200 GeV could in principle solve the problem. However, since the magnetic field in this model cannot exceed 15 μG , the only way to shift the Compton peak to sub-TeV energies is to assume that the supernova remnant is older than 10^4 yr .

An alternative solution for explanation of gamma-ray data within the IC models is to assume a higher density of relativistic electrons responsible for $\leq 1 \text{ TeV}$ gamma rays, i.e. to postulate a second, low-energy electron component in the shell. Formally this assumption does not *a priori* contradict the observations since the additional electrons are required to be present below 20 TeV, i.e. in the energy range which is not constrained by *Suzaku* observations (for production of the lowest energy X-rays detected by *Suzaku* in a magnetic field of 15 μG the electron energy must exceed 40 TeV). The results calculated under such assumption are shown in Figure 16. The second electron component is assumed to have a power-law injection spectrum with the same index as the first (main) component, $s = 2.0$, but with a high energy cutoff around 10 TeV. The latter is required to prevent the conflict with the observed gamma-ray spectrum above 1 TeV.

3.4.2. Morphology

A comparison between the X-ray and the TeV gamma-ray morphology is expected to provide information about the acceleration/emission processes. As is already shown in Figure 8, the *Suzaku* XIS image revealed a significant correlation with that of H.E.S.S. telescopes not only in the bright structures but also in the dim regions of the remnant. In the following, the two images are compared with each other on a more quantitative basis.

It should be taken into account that the X-ray morphology can be affected by the spatial distribution of absorption column density, N_H . In order to avoid the effect, here we disregard the energy band lower than 1 keV, and use two energy intervals, 2–5 keV and 5–10 keV, for comparison. For the N_H variation as shown in Table 3, the count rate can vary by 5% and 0.7% in the 2–5 keV band and 5–10 keV band, re-




FIG. 13.— Multi-wavelength spectral energy distribution (SED) of RX J1713.7–3946 with a hadronic model. The magnetic field is $200 \mu\text{G}$. The injection index of electrons and protons is 2.0, and constant injection during 1000 yr is assumed. For the IC flux, the contribution of each photon field is shown. The dashed line, the dash-dotted line, and the dotted line are IC flux of CMB, infrared, and optical photons, respectively. By taking 1 kpc as the distance of the SNR, the total energy of electrons is $W_e = 3.1 \times 10^{46}$ erg. The total proton energy is $W_p = 2.7 \times 10^{50} (n/1 \text{ cm}^{-3})^{-1}$ erg, where n is the ambient matter density.




FIG. 14.— The SED of RX J1713.7–3946 with a leptonic model. The injection index of electrons is 2.0. The calculation is for magnetic field strength of $14 \mu\text{G}$. The total energy of electrons is $W_e = 1.4 \times 10^{47}$ erg. The line styles for the IC spectra are the same as those in Figure 13.




FIG. 15.— Same as 14 but additional optical radiation is included as seed photons of IC scattering to fit the H.E.S.S. spectrum. The IC spectrum with the thin solid line and the dotted line correspond to the contribution of the interstellar radiation assumed in Figure 14 and the additional optical radiation, respectively. The thick solid line indicates the sum of the two. The energy density of the additional optical radiation is 140 eV cm^{-3} , which is about two orders of magnitude larger than the estimate by Porter et al. (2006).

spectively. One should also take into account the difference of point spread functions between *Suzaku* XIS and H.E.S.S. when comparing the two images. To prevent this, we compare surface brightness for each square region with a size of $10'.8 \times 10'.8$, which is larger than the point spread functions




FIG. 16.— Same as 14 but another electron population is added. The thin solid lines are radiation from each electron population and the thick solid line is the sum of the contributions from the two electron populations. The total energy of the second electron population is $W_e = 3.4 \times 10^{47}$ erg.

of either observatory. The regions are indicated with green dashed lines in Figure 17.

Figure 18 shows a scatter plot between the *Suzaku* XIS count rate (F_{keV}) and that of H.E.S.S. (F_{TeV}). As seen in this plot, the X-ray count maps correlate strongly with the gamma-ray count map. The correlation coefficients are calculated to be 0.85 and 0.83, for 2–5 keV band and 5–10 keV band, respectively. It is worth noting that there are some deviations (X-ray intensity excesses) in the bright regions. Figure 19 shows a map of $F_{\text{keV}} - F_{\text{TeV}}$ (for 2–5 keV band) overlaid with the H.E.S.S. contours, in which one can see that the X-ray excesses are present along the NW and SW rims.

4. DISCUSSION

4.1. Cutoff in the Synchrotron Spectrum

We conducted a series of *Suzaku* observations which covers about two-thirds of the surface of SNR RX J1713.7–3946. Through the data analysis, we successfully detected signals up to ~ 40 keV from each of the pointings. The HXD spectra above 10 keV are significantly steeper than those obtained from the XIS below 10 keV, suggesting that a spectral cutoff is common throughout the remnant. By combining the XIS and HXD spectra, we obtained a wide-band spectrum with high statistics, which clearly shows a cutoff around 10 keV.

Taking advantage of the high photon statistics, we performed a detailed study of the cutoff shape and compared it with a recent theoretical prediction by Zirakashvili & Aharonian (2007). A sharp cutoff of the accelerated electron spectrum is needed to reproduce the cutoff shape in the synchrotron spectrum detected with *Suzaku*. The spectrum of electrons derived from *Suzaku* data is in good agreement with the analytical model of Zirakashvili & Aharonian (2007).

The cutoff energy in the spectrum of synchrotron radiation contains an important information about the efficiency of diffusive shock acceleration. For acceleration in the Bohm diffusion regime and when energy losses of electrons are dominated by synchrotron cooling, the cutoff energy, ε_0 in equation (9) is expressed as (Zirakashvili & Aharonian 2007)

$$\varepsilon_0 = 0.55 \left(\frac{v_s}{3000 \text{ km s}^{-1}} \right)^2 \eta^{-1} \text{ keV}, \quad (11)$$

where v_s is the shock speed and $\eta (\geq 1)$ is the so-called “gyrofactor”. The case of $\eta = 1$ corresponds to the “Bohm limit”, and implies high level of turbulence $\delta B \sim B$. The *Suzaku* spectrum is characterized by the best-fit parameter $\varepsilon_0 = 0.67$ keV which gives $v_s = 3300\eta^{1/2} \text{ km s}^{-1}$. Here, we assume that




FIG. 17.— The regions for comparison of the X-ray and the TeV gamma-ray morphologies overlaid on the XIS image (2–5 keV) (upper panel) and the H.E.S.S. image (Aharonian et al. 2007) (lower panel). The size of each square region is $10'.8 \times 10'.8$. The results of the comparison are shown in Figure 18 and Figure 19.




FIG. 18.— The scatter plot of X-ray surface brightness from the XIS and the gamma rays from H.E.S.S. for each square region shown in Figure 17. Each data set is scaled for direct comparison.




FIG. 19.— The map of $F_{\text{keV}} - F_{\text{TeV}}$, both of which are plotted in Figure 18. The values of F_{keV} are those for the energy range of 2–5 keV. The overlaid contours are the H.E.S.S. image taken from Aharonian et al. (2007).

the shock speed v_s is uniform throughout the remnant, which is supported by the fact that the outer boundary of the X-ray morphology is nearly circular. The upper-limit of the shock speed $v_s \leq 4500 \text{ km s}^{-1}$ derived from the *Chandra* data (Uchiyama et al. 2007), results in $\eta \leq 1.8$. This is a strong evidence of acceleration of electrons in the regime close to the Bohm limit. Note that a similar result was obtained for the SW rim of the remnant in Uchiyama et al. (2007). Here we confirm this conclusion for a larger area of the remnant with higher statistics.

4.2. Multi-wavelength Spectrum

While there is little doubt in the synchrotron origin of broad-band X-ray emission measured by *Suzaku*, the X-ray spectrum alone does not give preference to the strength of the magnetic field in the region of production of synchrotron radiation. Formally, the field can be as small as $10 \mu\text{G}$ and as large as $100 \mu\text{G}$. Meanwhile, the strength of the magnetic field has dramatic impact on the origin of TeV gamma-rays. The so-called leptonic or inverse Compton models require magnetic field between $10 \mu\text{G}$ and $15 \mu\text{G}$. Even so, it is difficult to achieve, at least within a simple one-zone model, a satisfactory explanation of both X-ray and TeV gamma-ray spectral features, unless we invoke an extremely high diffuse radiation field of optical photons to enhance the IC gamma-radiation below 1 TeV (see Figure 15). A more realistic approach for explanation of the broad-band TeV gamma-ray spectrum within IC models can be realized under the assumption of existence an additional, low-energy electron component in the shell (see Figure 16). Even so, the most serious problem for IC models remains the requirement of low magnetic field in the gamma-ray production region, in contrast to large magnetic field required to explain the fast variability of X-ray emission on small scales. Formally, one may assume that gamma-rays are mainly produced in "voids", i.e. in regions with very low magnetic field. This would imply quite inhomogeneous distribution of the magnetic field in the shell. One the other hand, the observed strong X-ray and TeV correlation within the IC models can be explained only in the case of homogeneous distribution of magnetic field.

The large-scale magnetic fields on parsec scales with an average strength larger than $\geq 15 \mu\text{G}$ make the IC gamma-ray production inefficient, and thus give preference to the so-




FIG. 20.— The SED of RX J1713.7–3946 from radio to X-ray with a synchrotron model curve calculated by assuming $B = 100 \mu\text{G}$.

called hadronic models of gamma-rays produced at interactions of accelerated protons with the ambient gas via production and decay of secondary π^0 -mesons. What concerns X-rays, they are produced, as in leptonic models, by synchrotron radiation of directly accelerated electrons. This is demonstrated in Figure 13 for very strong magnetic field, $B = 200 \mu\text{G}$. Note that while comparing the model predictions with measurements in the radio band, one should take into account that the radio points shown correspond to measurements of NW rim, while the X-ray and gamma-ray points are for the entire remnant. If the ratio of the radio flux from the NW rim to that from the whole remnant is not much different from the corresponding ratio in X-rays, the flux from the whole SNR should be significantly larger. This would reduce the difference between the measurements and predictions. In any case, the radio flux can be significantly reduced assuming somewhat smaller magnetic field or harder electron spectrum. Indeed, in Figure 20 we show model calculations performed for a magnetic field $B = 100 \mu\text{G}$. While the synchrotron X-ray flux is described perfectly as before (in Figure 13), the radio flux is by a factor of four lower; at 1.4 GHz it is 34 Jy, which is close to the latest estimates of radio flux from the whole remnant based on observations with ATCA and the 30-m radio telescopes of IRA (F. Acero et al. 2008, in preparation; G. Dubner 2008, private communications).

The radio flux can be suppressed even for the ambient field larger than $100 \mu\text{G}$, provided that the electron injection spectrum is harder than E^{-2} . Figure 21 demonstrates this possibility, where we assume an electron/proton index of $s = 1.7$ which corresponds to a compression ratio of $\sigma = 5.3$. Note that σ can exceed the adiabatic upper limit of 4 as described by Berezhko & Völk (2006). Note that the value of $s = 1.7$ is consistent with the conclusion of Villante & Vissani (2007) based on semi-analytical derivation of the parent proton spectrum from the H.E.S.S. data. In model calculations shown in Figure 21, the spectrum of protons requires an “early” exponential cutoff at $E_{p0} = 25.0 \text{ TeV}$. Note that formally the spectral index $s = 1.7$ implies shock acceleration in non-linear regime which in fact predicts some deviation from pure power-law distribution of accelerated particles (see e.g. Ellison et al. 2007; Berezhko & Völk 2006). This would lead to further reduction of the radio flux.

The convection of low energy electrons could be another reason for low radio flux. Note that the escape of electrons through convection has strong impact only on low energy electrons; because of fast synchrotron cooling, the effect of




FIG. 21.— The SED of RX J1713.7–3946 with a hadronic model when the index of the electron/proton spectrum is 1.7. The magnetic field is $200 \mu\text{G}$. The line styles for the IC spectra are the same as those in Figure 13 the total energy of electrons is $W_e = 6.0 \times 10^{45} \text{ erg}$. The total proton energy is $W_p = 1.6 \times 10^{50} (n/1 \text{ cm}^{-3})^{-1} \text{ erg}$.

escape is negligible for multi-TeV electrons. A significant quantity of low-energy electrons can escape from the shell of the SNR before emitting radio photons. Therefore, the radio flux can be reduced while the X-ray flux will remain unchanged.

For calculations shown in Figure 13, the total energy of electrons is estimated as $W_e = 3.1 \times 10^{46} (d/1 \text{ kpc})^2 \text{ erg}$, and the energy for protons as $W_p = 2.7 \times 10^{50} (n/1 \text{ cm}^{-3})^{-1} (d/1 \text{ kpc})^2 \text{ erg}$. In the case of harder energy spectra with power-law index $s = 1.7$ corresponding to Figure 21, one has $W_e = 6.0 \times 10^{45} (d/1 \text{ kpc})^2 \text{ erg}$, and $W_p = 1.6 \times 10^{50} (n/1 \text{ cm}^{-3})^{-1} (d/1 \text{ kpc})^2 \text{ erg}$, respectively. The proton/electron ratio in either case is very small, $K_{ep} \leq 10^{-4} (n/1 \text{ cm}^{-3})$. This value is significantly smaller than that for directly observed local cosmic rays ($K_{ep} \sim 0.01$), unless a large ambient matter density of $n \sim 100 \text{ cm}^{-3}$ is assumed. Katz & Waxman (2008) and Butt et al. (2008) argued that the hadronic scenario for this SNR has difficulties because the K_{ep} value should be consistent with local cosmic rays and other SNRs. However, the K_{ep} value of one SNR at a fixed age does not necessarily need to agree with the local cosmic ray value. The low-energy electrons are likely produced in later stages of SNR evolution, when the K_{ep} value can be different from the present value. A comparison with other SNRs should be performed with care, as well.

Cutoff energy in the gamma-ray spectrum should give an important hint whether SNRs are sources of cosmic rays below the *knee*, if gamma rays observed by H.E.S.S. have hadronic origins. Plaga (2008) argued that the cutoff energy of the H.E.S.S. spectrum of RX J1713–3946 is around 18 TeV, which can be translated to proton energy more than 10 times below the energy of the *knee*. Indeed our multi-wavelength study requires a cutoff in the proton spectrum around 100 TeV or even less for hard acceleration spectra of protons. However, one should take into account that even in the case of effective acceleration the highest energy protons beyond 100 TeV escape the source in a quite short time scales, and hence do not contribute to the gamma-ray production at the present epoch (Ptuskin & Zirakashvili 2005; Gabici & Aharonian 2007).

A unique feature of RX J 1713.7–3946 is the lack of thermal X-ray emission. Recently, Katz & Waxman (2008) and Butt et al. (2008) interpreted this fact as an argument against the hadronic model for TeV gamma rays. Generally it is true that plasma in young supernova remnants is heated to high temperatures observed via thermal X-ray emission of hot electrons. However, one should take into account that we deal

with a unique object, and the lack of thermal X-ray emission cannot *a priori* be invoked as an argument against the hadronic origin of the observed TeV gamma rays.

It is important to note that in SNR shocks the formation of high plasma temperatures with $kT_i = 3/16 m_i v_s^2$ is relevant only to protons (ions), and that a high ion temperature does not automatically (from first principles) mean a high electron temperature. In fact, the only known heating process of thermal electrons is Coulomb collisions between electrons and protons (ions), which, however, has too long time scale to establish electron-proton equipartition. On the other hand, we do know from X-ray observations that the electrons in young SNRs are heated to keV temperatures. This can be explained by assuming that a hypothetical mechanism, most likely related to the energy exchange through excited plasma waves, is responsible for effective electron heating in SNRs. As long as the nature of this mechanism in collisionless shocks remains unknown, one cannot predict, even qualitatively, the specifics of its operation on a source by source basis.

We indeed deal with two interesting facts. First, many young SNRs, like Tycho and Cassiopeia A, with intense thermal X-ray emission and intense nonthermal radio emission emit little (or do not emit at all) TeV gamma rays. On the other hand, RX J1713.7–3946, with lack of (or rather very low) thermal X-ray emission and with relatively weak non-thermal radio emission, is a source of powerful TeV radiation. These two facts can be treated as a hint for low efficiency of establishing equipartition in the thermal plasma in very effective TeV particle accelerators like RX J1713.7–3946. It is interesting to note in this regard, that such a tendency is found also for another effective TeV accelerator — SN 1006 (Vink et al. 2003). Whether the reduction of the exchange rate between different particle species in thermal plasma has a link to the particle acceleration in high Mach number shocks, as proposed by Vink et al. (2003), is a very interesting question to be explored in future deep theoretical and phenomenological studies. In this regard, RX J1713.7–3946 can serve as a key “template” source for such studies.

Hughes et al. (2000) also discussed low electron temperature based on *Chandra* observations of a young SNR in the Small Magellanic Cloud, 1E 0102.2–7219. They measured a blast-wave velocity of $\sim 6000 \text{ km s}^{-1}$ from the expansion rate and predicted the electron temperature of $kT_e > 2.5 \text{ keV}$ by considering Coulomb heating. However, the electron temperature derived from their spectral analysis is 0.5 keV , which is far below the prediction. According to their discussion, not only electron heating but also ion heating is suppressed and substantial fraction of energy may be going into cosmic-ray production due to the non-linear effects in the shock.

The nonlinear shock acceleration in this object can convert a significant, up to $f \sim 0.5$ fraction of the kinetic energy of explosion into relativistic particles. Correspondingly the fraction of available energy which goes to the heating of the ambient plasma will be reduced $1 - f \sim 0.5$. Yet, conservative estimates show that plasma in RX J1713.7–3946 can be heated to quite high temperatures even the heating of electrons and protons proceeds only through the Coulomb exchange. This question recently has studied by Ellison et al. (2007) for a standard SNR of age $t_{\text{SNR}} = 500 \text{ yr}$ and energy $E_{\text{SN}} = 10^{51} \text{ erg}$. In particular, it has been shown that in the case of effective diffusive shock acceleration and the plasma density $n = 0.1 \text{ cm}^{-3}$, the ratio of synchrotron luminosity to thermal (bremsstrahlung) luminosity can be as large as 100. This implies that in the case of RX J1713.7–3946, from which

thermal X-ray emission is not observed, the plasma density cannot significantly exceed 0.1 cm^{-3} (the luminosity of thermal bremsstrahlung is proportional to n^2). The low density of order of 0.1 cm^{-3} reduces the parameter space for hadronic models but does not exclude it. Indeed, as mentioned above, the TeV gamma-ray flux of RX J1713.7–3946 can be explained by interactions of protons if the parameter $A = (W_p/10^{50} \text{ erg})(n/1 \text{ cm}^{-3})(d/1 \text{ kpc})^{-2}$ exceeds 1.5 to 3, depending on the spectrum of protons. Assuming that more than 30% of the explosion energy of this SNR is released in accelerated protons, and that the plasma in the gamma-ray production region is compressed by a factor of few, we find that the located of the source at a distance of about 1 kpc would marginally support the hadronic model. While closer location of the source would make the model requirements quite viable and flexible, the location of the source beyond 1 kpc hardly can be accommodated within a standard shock acceleration scenario. If the SNR is closer, the distance of $d \gtrsim 0.5 \text{ kpc}$ seems reasonable considering the upper limit on the shock speed of $4500(d/1 \text{ kpc}) \text{ km s}^{-1}$ by Uchiyama et al. (2007).

Finally we should mention the model suggested by Malkov et al. (2005) which can naturally explain both the low synchrotron flux at radio frequencies and lack of thermal X-ray emission of RX J1713.7–3946. The standard scenarios of gamma-ray production in SNRs assume that radiation is produced in downstream where the density of both relativistic particles and thermal plasma is higher than in upstream. However, in the cases when the shock is expanding into a low-density wind bubble and approaching cold dense material, e.g. swept-up shell or surrounding molecular clouds, the gamma-radiation is contributed predominantly from upstream. While the energy distribution of accelerated particles downstream is coordinate-independent in both linear and nonlinear regimes, the particle distribution upstream is coordinate-dependent. Because of energy-dependent diffusion coefficient, the high-energy particles diffuse ahead of low-energy particles, thus a dense material adjacent upstream will “see” relativistic particles (protons and electrons) with low-energy exponential cut-off, E_{min} , which depends on the location of the dense regions. This implies that the effective production of TeV gamma-rays (from p - p interactions) and X-rays (from synchrotron radiation of TeV electrons) will be not accompanied by low energy (GeV) gamma-rays and synchrotron radio emission. Obviously, this model is not constraint by lack of thermal emission.

4.3. Morphology

In addition to the spectral information, the comparison of X-ray and TeV gamma-ray images presented in Figure 18 helps us to draw the physical picture of RX J1713.7–3946. Let us first discuss the tight correlation observed in most parts of the remnant. Within the hypothesis of hadronic origin of gamma-rays, the gamma-ray flux is proportional to the number densities of the ambient matter and relativistic protons, while the X-ray flux is proportional to number density of electrons. If the matter distribution significantly varies throughout the SNR, we need fine parameter tuning among the matter distribution, the electron injection rate, and the proton injection rate, in order to produce the tight correlation. Therefore, more natural explanation is that the matter density is uniform and the injection rate of the electrons and that of the protons are proportional to each other.

The X-ray flux excess along the NW and SW rims provides a unique probe of recent acceleration activity. Let us consider




FIG. 22.— The same plot as Figure 18 but results obtained by assuming the “toy” model described in the text.

a “toy” model and compare its predictions with the observational results. In the toy model, the injection rate of electrons and protons keeps constant but increases by a factor of 1.5 in the last 10 yr only at the NW and SW rims. What is important here is the difference of cooling time between electrons and protons. The synchrotron cooling time of an electron emitting synchrotron photons with energy of ε is given as equation (6), while the cooling time of protons due to p - p interactions is expressed as

$$t_{pp} = 5.3 \times 10^7 \left(\frac{n}{1 \text{ cm}^{-3}} \right)^{-1} \text{ yr} \quad (12)$$

and is almost energy-independent. For the magnetic field $B = 100 \mu\text{G}$, the cooling times of electrons emitting 2 keV and 5 keV X-rays are 12 yr and 7.6 yr, respectively. For any reasonable density of ambient gas, the cooling time of protons is much longer than the lifetime of this SNR. While the synchrotron X-rays we observe at present are emitted by electrons accelerated during the last ~ 10 yr, the flux of π^0 -decay gamma rays is provided by protons accelerated throughout the lifetime of the SNR. Figure 22 shows the scatter plot of F_{keV} and F_{TeV} expected from the toy model, which shows a similar distribution to the observational results in Figure 18. The recent active acceleration increases the X-ray flux while keeping the gamma-ray flux almost unchanged.

5. SUMMARY

We observed SNR RX J1713.7–3946 with the *Suzaku* observatory. Hard X-rays up to ~ 40 keV are detected from each of the 11 pointings. The hard X-ray morphology estimated by the HXD PIN data is generally consistent with an extrapolation of that in the energy region below 10 keV. When the HXD spectra are fitted with a power law, the photon indices are larger than those obtained from the XIS data. The difference of photon indices between the XIS and the HXD varies from region to region. Although this may suggest a variation of spectral shape or cutoff energy, the FoV of the HXD PIN is not small enough to allow detailed imaging spectroscopy. Such studies will become possible with upcoming missions with hard X-ray mirrors like *NeXT*, *NuS-TAR*, or *Simbol-X*. Moreover these missions will extend the

effective studies up to 100 keV. If the TeV gamma-ray emission of RX J1713.7–3946 is of hadronic origin, this should allow detection and study of synchrotron X-ray emission of electrons produced in proton-proton interactions via decays of secondary charged pions (Aharonian 2004). In this regard, the above mentioned missions can provide very effective tools for deep (at the level as low as $10^{-13} \text{ erg cm}^{-2} \text{ s}^{-1}$) probes of hadronic processes in SNRs in the ≥ 100 TeV energy regime with unprecedented (subarcmin) angular resolution.

Using the XIS and HXD data, we obtained a synchrotron spectrum in the energy range of two decades (0.4–40 keV), which means we can probe the parent electron distribution in the energy range of one decade regardless of the magnetic field strength. The wide-band coverage enables us to see a clear high-energy cutoff in the synchrotron spectrum, and for the first time allows detailed studies of the cutoff shape and derivation of the spectrum of the parent electrons. The spectral shape in the cutoff region was quantitatively evaluated, which revealed that the cutoff shape is compatible with a theoretical prediction by Zirakashvili & Aharonian (2007). Based on their model, the cutoff energy is obtained as $\varepsilon_0 = 0.67 \pm 0.02$ keV. This result, together with upper limit of the shock velocity from *Chandra* (Uchiyama et al. 2007), indicates that acceleration efficiency in this remnant approaches the Bohm limit.

We modeled the multi-wavelength spectrum of RX J1713.7–3946 within both the leptonic and hadronic gamma-ray production scenarios. The hadronic model nicely fits the data while it seems difficult to explain all observational data with a simple leptonic model. The major problem with leptonic models is related to the requirement of low magnetic field, $B \leq 15 \mu\text{G}$ which does not agree with the recent discovery of variability of local regions of the shell on year timescales. The hadronic models recently have been criticized based on the lack of thermal emission and low radio flux. However, these facts can be accommodated within a standard shock acceleration model in a young SNR with magnetic field as large as $100 \mu\text{G}$, plasma density $n \sim 0.1 \text{ cm}^{-3}$, and distance to the source $d \leq 1$ kpc, assuming that more than 30% of energy of explosion is released in relativistic protons with spectrum as hard as E^{-2} and exponential cutoff around 100 TeV.

Finally, besides the general strong correlation between X-ray and TeV gamma-ray emission, we found an excess X-ray emission compared to gamma-ray emission in the brightest regions of the remnant. This excess can be explained by recent activity accompanied by effective acceleration of electrons in localised regions of the shell.

The authors would like to thank all the members of the *Suzaku* Science Working Group for their help in the spacecraft operation, instrumental calibration, and data processing. The authors thank Una Hwang for carefully reading the manuscript and Stefan Funk for assisting with the comparison of the morphologies with the H.E.S.S. data and for his helpful comments on the manuscript. The authors also thank Misha Malkov and Vladimir Zirakashvili for discussions related to different aspects of the diffusive shock acceleration theory. T. Tanaka and A. Bamba are supported by research fellowships of the Japan Society for the Promotion of Science for Young Scientists.

REFERENCES

- Aharonian, F. A., et al. 2001, *A&A*, 370, 112
- Aharonian, F. A. 2004, *Very High Energy Cosmic Gamma Radiation: A Crucial Window on the Extreme Universe* (World Scientific)
- Aharonian, F. A., et al. 2004, *Nature*, 432, 75
- Aharonian, F. A., et al. 2006, *A&A*, 449, 223
- Aharonian, F. A., et al. 2007, *A&A*, 464, 235
- Berezhko, E. G., & Völk, H. J. 2006, *A&A*, 451, 981
- Bird, A. J., et al. 2006, *ApJ*, 636, 765
- Blandford, R., & Eichler, D. 1987, *Phys. Rep.*, 154, 1
- Butt, Y., Porter, T., Katz, B., & Waxman, E. 2008, *MNRAS*, in press
- Cassam-Chenaï, G., Decourchelle, A., Ballet, J., Sauvageot, J.-L., Dubner, G., & Giacani, E. 2004, *A&A*, 427, 199
- Ellison, D.C., Patnaude, D.J., Slane, P., Blasi, P., Gabici, S. 2007, *ApJ*, 661, 879
- Enomoto, R., et al. 2002, *Nature*, 416, 823
- Fukui, Y., et al. 2003, *PASJ*, 55, L61
- Gabici, S., & Aharonian, F. A. 2007, *ApJ*, 665, L131
- Gruber, D. E. Matteson, J. L.; Peterson, L. E., & Jung, G. V. 1999, *ApJ*, 520, 124
- Hartman, R. C., et al. 1999, *ApJS*, 123, 79
- Hiraga, J. S., Uchiyama, Y., Takahashi, T., & Aharonian, F. A. 2005, *A&A*, 431, 953
- Hughes, J. P., Rakowski, C. E., & Decourchelle, A. 2000, *ApJ*, 543, L61
- Ishida, M., et al. 2006, *Suzaku Memo*, JX-ISAS-SUZAKU-MEMO-2006-40
- Ishisaki, Y., et al. 2007, *PASJ*, 59, S113
- Katz, B., & Waxman, E. 2008, *Journal of Cosmology and Astroparticle physics*, in press
- Kelner, S. R., Aharonian, F. A., & Bugayov, V. V. 2006, *Phys. Rev. D*, 74, 034018
- Kokubun, M., et al. 2007, *PASJ*, 59, S53
- Koyama, K., Petre, R., Gotthelf, E. V., Hwang, U., Matsuura, M., Ozaki, M., & Holt, S. S. 1996, *Nature*, 378, 255
- Koyama, K., Kinugasa, K., Matsuzaki, K., Nishiuchi, M., Sugizaki, M., Torii, K., Yamauchi, S., & Aschenbach, B. 1997, *PASJ*, 49, L7
- Koyama, K., et al. 2007, *PASJ*, 59, S23
- Lazendic, J. S., Slane, P. O., Gaensler, B. M., Plucinsky, P. P., Hughes, J. P., Galloway, D. K., & Crawford, F. 2003, *ApJ*, 593, L23
- Lazendic, J. S., Slane, P. O., Gaensler, B. M., Reynolds, S. P., Plucinsky, P. P., & Hughes, J. P. 2004, *ApJ*, 602, L201
- Malkov, M.A., Diamond, P.H., Sagdeev, R.Z. 2005, *ApJ*, 624, L37
- Malkov, M. A., and Drury, L. O'C. 2001, *Rep. Prog. Phys.*, 64, 429
- Mitsuda, K., et al. 2007, *PASJ*, 59, S1
- Mizuno, T., et al. 2006, *Suzaku Memo*, JX-ISAS-SUZAKU-MEMO-2006-42
- Moriguchi, Y., Tamura, K., Tawara, Y., Sasago, H., Yamaoka, K., Onishi, T., & Fukui, Y. 2005, *ApJ*, 631, 947
- Muraishi, H., et al. 2000, *A&A*, 354, L57
- Pfeffermann, E., & Aschenbach, B. 1996, in *Röntgenstrahlung from the Universe*, ed. H. U. Zimmermann, J. Trümper, & H. Yorke, *MPE Rep.*, 263, 267
- Plaga, R. 2008, *Nature*, 453, 48
- Porter, T. A., Moskalenko, I. V., & Strong, A. W. 2006, *ApJ*, 648, L29
- Ptushkin, V. S., & Zirakashvili, V. N. 2005, *A&A*, 429, 755
- Serlemitsos, P. J., et al. 2007, *PASJ*, 59, S9
- Slane, P., Gaensler, B. M., Dame, T. M., Hughes, J. P., Plucinsky, P. P., & Green, A., 1999, *ApJ*, 525, 357
- Slane, P., Hughes, J. P., Edgar, R. J., Plucinsky, P. P., Miyata, E., Tsunemi, H., & Aschenbach, B. 2001, *ApJ*, 548, 814
- Takahashi, T., et al. 2007, *PASJ*, 59, S35
- Takahashi, T., et al. 2008, *PASJ*, 60, S131 (Paper I)
- Terada, Y., et al. 2005, *IEEE Trans. Nucl. Sci.*, 52, 902
- Uchiyama, Y., Aharonian, F. A., & Takahashi, T. 2003, *A&A*, 400, 567
- Uchiyama, Y., Aharonian, F. A., Takahashi, T., Hiraga, J. S., Moriguchi, Y., & Fukui, Y. 2005, *High Energy Gamma-Ray Astronomy*, 745, 305
- Uchiyama, Y., Aharonian, F. A., Tanaka, T., Takahashi, T., & Maeda, Y. 2007, *Nature*, 449, 576
- Villante, F. L., & Vissani, F. 2007, *Phys. Rev. D*, 76, 125019
- Vink, J., Laming, J. M., Gu, M. F., Rasmussen, A., & Kaastra, J. S. 2003, *ApJ*, 587, L31
- Wang, Z. R., Qu, Q.-Y., & Chen, Y. 1997 *A&A*, 318, L59
- Watanabe, S., et al. 2007, *Suzaku Memo*, JX-ISAS-SUZAKU-MEMO-2007-01
- Zirakashvili, V. N., & Aharonian, F. 2007 *A&A*, 465, 695